

QUOTATION



Date: 24-02-26

Quote Ref.: QT-EJT-ELAF-CCTV-030226-R04

Eng. Ref: AF102

To: Ellaf

Attn.:

From: Eng. A. Farouk

Cont.:+966560798144

SUB.: PROPOSAL OF CCTV SYSTEM For Ellaf

SCOPE: Supply, Termination, Installation, Arrangement, Testing, and Labelling.

Dear Sir,

We thank you for your subject enquiry and have pleasure in putting together a comprehensive proposal for the same. We hope this is in line with your requirements and that you will favour us with your order.

SUMMARY

No.	System	Total Price
Supply, Termination, Installation, Arrangement, Testing, and Labelling.		
1	CCTV SYSTEM (Hikvision)	128,999.00
2	SCS SYSTEM (Datwyler)	118,538.00
3	ACT SYSTEM (H3C)	172,955.00
Total (SAR)		420,492.00
VAT (15%)		63,073.80
Grand Total		483,565.80

Terms & conditions

Price	All prices are in Saudi Riyals. Any change in quantity will require a requote and will make this proposal null and void
Payment Terms	70% Advance, and 30% Before Delivery.
Offer Validity	2 Weeks
Delivery Terms	12-16 Weeks on receipt of confirmed PO and confirmation of payment terms, Delivery terms are estimates.
Scope of Work	Supply, Termination, Installation, Arrangement, Testing, and Labelling.
Warranty	24 months from the date of supply against manufacturing defects.
Notes:	Quotation based on the BOQ, Any variation from the BOQ will be charged extra.
Exclusions	Shop Drawings, Passive components (Ceiling hole opening, Civil Work, Electrical cables, Power cables, Manholes, Handholes, Duct, Electrical Work, EMT Conduits, PVC Conduits, and any machine required to do the high ceiling work Printers, Routers, Firewalls are out of scope.
Notes:	Exclude Additional Warranty, Preventive Maintenance & Spares.

In the meantime, should you have any questions or need to discuss the commercials in greater detail, please do not hesitate to contact the undersigned.

We thank you for your support to **EJ TECH** and look forward to the pleasure of doing business.

With best regards,

Prepared By:
Samar Hussein
Pre-Sales Engineer

Managed by:
Mohamed Farouk
Service Delivery Manager

المملكة العربية السعودية - الرياض - شارع العليا العام - العقارية ٢ - مكتب رقم ٨١٣ - ص.ب ٣٠٠٧٢٠ الرمز ١١٣٧٢ س.ت ١٠١٠٢٤١٠٨٣
Kingdom of Saudi Arabia - Riyadh - Al Olaya street - Akaria 2 - Office No. 813 - P.O Box 300720 Code 11372 - C.R. 1010241083

+966 11 460 0121 +966 11 460 0114

www.ejt.sa

+966 11 460 0114 +966 11 460 0121

Date: 24-02-26

Quote Ref.: QT-EJT-ELAF-CCTV-030226-R04

SUB.: PROPOSAL OF CCTV SYSTEM For Ellaf

SCOPE: Supply, Termination, Installation, Arrangement, Testing, and Labelling.

S.#	ITEM CODE	ITEM DESCRIPTION	UOM	QTY	UNIT PRICE	TOTAL
		IP SURVEILLANCE SYSTEM				
		Cameras				
1	DS-2CD3041G2E-LIU(4mm)	4 MP Fixed Bullet Network Camera	Ea	40	250.00	10,000.00
2	DS-1280ZJ-XS	Junction Box	Ea	40	34.00	1,360.00
3	DS-2CD3141G2-LIUF(2.8mm)	4 MP Smart Hybrid Light Motion 2.0 Fixed Mini Dome Network Camera	Ea	145	273.00	39,585.00
4	DS-1280ZJ-DM46	Junction Box	Ea	145	25.00	3,625.00
		Recording & Storage (31 Days , H265 , 2mp , 25 FPS)				
5	DS-96128NI-M8	128-ch 3U 4K NVR	Ea	1	7,520.00	7,520.00
6	M8(STD)/Saudi	64-ch 3U 4K NVR	Ea	1	4,488.00	4,488.00
7	WUS721210BLE6L4	HDD 10TB	Ea	15	1,575.00	23,625.00
		Workstations & Displays				
8	DS-VE41-T/HW5	Tower Workstation	Ea	1	6,283.00	6,283.00
9	DS-D5043F3-1V0S	43 inch FHD 60Hz VA Monitor	Ea	4	1,097.00	4,388.00
10	DS-D5024F2-5V2(O-STD)(EU)	23.8 inch FHD 100Hz VA Monitor	Ea	1	399.00	Option
		Professional Services				
11	SRV	Devices Installation, Testing & Commissioning	Lot	1	28,125.00	28,125.00
					Total Excluding VAT	128,999.00

Date: 24-02-26

Quote Ref.: QT-EJT-ELAF-CCTV-030226-R04

SUB.: PROPOSAL OF CCTV SYSTEM For Ellaf

SCOPE: Supply, Termination, Installation, Arrangement, Testing, and Labelling.

S.#	ITEM CODE	ITEM DESCRIPTION	UOM	QTY	UNIT PRICE	TOTAL
		SCS				
		Cameras				
1	19463100CP	Cat 6 Data Cable U/UTP 4 Pairs, 250MHz,23AWG, FRNC/LSOH Sheath ,Orange Color (305Meter/Roll) -Datwyler.	Ea	83	420.00	34,860.00
2	418022	24 Ports Cat 6 Patch Panel 19" 1U, Empty, Black Color -Datwyler.	Ea	14	106.00	1,484.00
3	418070	Cat 6 RJ-45 Module Keystone White -Datwyler.	Ea	336	11.00	3,696.00
4	4000699	1U Cable Mangment 19" with Cover -Datwyler.	Ea	14	43.00	602.00
5	RJ-45	Male connector RJ-45 With 10% Spare	Ea	204	6.00	1,224.00
6	309321	Cat 6 Patch Cord U/UTP , LSOH Sheath ,Grey Color, 1 Meter - Datwyler. With 10% Spare	Ea	204	12.00	2,448.00
		Fiber Solution				
7	19011200DZ	6C Fibre Optic Cable MM(OM3-50/125µm), Loose Tube, Glass Armoured, Indoor/Outdoor LSOH Sheath -Datwyler.	Meter		6.00	-
8	41521200ZY	Fibre Patch Panel 1U 12 LC (6 LCD) Multi Mode, full Loaded with Adapters, Ceramic Sleeve and 12 Pigtaills MM OM3 2meter -Datwyler.	Ea	11	583.00	6,413.00
9	1411153	Splice holder for up to 6 splices (heat shrink technology) -Datwyler.	Ea	22	7.00	154.00
10	41522000ZY	Fibre Patch Panel 1U 48 LC (24 LCD) Multi Mode, full Loaded with Adapters, Ceramic Sleeve and 48 Pigtaills MM OM3 2meter -Datwyler.	Ea	2	1,271.00	2,542.00
11	1411153	Splice holder for up to 6 splices (heat shrink technology) -Datwyler.	Ea	16	7.00	112.00
12	423333	Fibre Optic Patch Cord MM 50/125 OM3 LC-LC Duplex 3Meter -Datwyler. With 10% Spare	Ea	48	70.00	3,360.00
		Network Cabinet				
13	4000610	42U Floor standing cabinet 800 x 1000mm with accessories (4Fans,1x6way PDU & 2pcs vertical cable manager2pcs Shelves) -Datwyler.	Ea	1	3,018.00	3,018.00
14	4001151	18U Wall Mounted cabinet 600 x 600mm with accessories - Datwyler.	Ea	11	1,525.00	16,775.00
		Professional Services				
15	SRV	CAT6 Termination,F.O Splicing, Cabinet Installation, Arrangement, and Labelling both ends	Lot	1	41,850.00	41,850.00
					Total Excuding VAT	118,538.00

Date: 24-02-26

Quote Ref.: QT-EJT-ELAF-CCTV-030226-R04

SUB.: PROPOSAL OF CCTV SYSTEM For Ellaf

SCOPE: Supply, Termination, Installation, Arrangement, Testing, and Labelling.

S.#	ITEM CODE	ITEM DESCRIPTION	UOM	QTY	UNIT PRICE	TOTAL
		ACT				
		Core Switch				
1	H3C S6520X-54HF-EI	H3C S6520X-54HF-EI L3 Ethernet Switch with 48*SFP Plus Ports and 6*QSFP28 Ports,Without Power Supplies	Ea	1	15,334.00	15,334.00
2		AC Jumper Cord,2.0m,1.0mm^2,Black,C14C(3P)STM250V10A,227 IEC 53(RVV)&H05VV-F&SJT,C13,CCC/UL/EU/KC	Ea	2	8.00	16.00
3	SFP-XG-SX-MM850-D	SFP+ Module(850nm,300m,LC)	Ea	14	532.00	7,448.00
4	SFP-GE-T-D	SFP GE Copper Interface Transceiver Module (100m,RJ45)	Ea	2	570.00	1,140.00
5	PSR180-12A-B	180W Asset-Managed AC Power Supply Module (Power Panel Side Exhaust)	Ea	2	657.00	1,314.00
6	LSPM1FANSB-SN	H3C Fan Module (Fan Panel Side Exhaust Airflow)	Ea	3	383.00	1,149.00
7		1Y 5x9 NBD-S CT Foundation BASIC Service, Global Version	Ea	2	1,524.00	3,048.00
		Access Switch 24 Port				
8	H3C S5136S-24P4X-EI	H3C S5136S-24P4X-EI Ethernet Switch with 24*10/100/1000BASE-T PoE+ Ports and 4*1G/10GBASE-X SFP+ Ports,(AC)	Ea	14	3,023.00	42,322.00
9	SFP-XG-SX-MM850-D	SFP+ Module(850nm,300m,LC)	Ea	14	532.00	7,448.00
10	LSWM2STK	SFP+ Cable 1.2m	Ea	14	416.00	5,824.00
11	SV-MA-CT-BS8-INT	1Y 5x9 NBD-S CT Foundation BASIC Service, Global Version	Ea	2	899.00	1,798.00
12	SV-MA-CT-BS8-INT	1Y 5x9 NBD-S CT Foundation BASIC Service, Global Version	Ea	3	2,892.00	8,676.00
		UPS				
13	40014700ZY	3 kVA Online UPS, Tower or/2U Rack Mounted(Additional Accessories), Rotable LCD screen, I/O Single Phase 230V, Built in 6X9AH Batteries, (2 Years Warranty)	Ea	1	3,734.00	3,734.00
14	40015200ZY	3kVA Battery Pack Module, Tower or/2U Rack Mounted (Additional Accessories)with Built in 12 X12V/9AH batteries for (15 Minutes), (1 Year Warranty)	Ea	1	2,467.00	2,467.00
15	40014640ZY	1 kVA Online UPS, Tower or/2U Rack Mounted(Additional Accessories), Rotable LCD screen, I/O Single Phase 230V, Built in 2X9AH Batteries, (2 Years Warranty)	Ea	11	1,800.00	19,800.00
16	40015000ZY	1 kVA Battery Pack Module, Tower or/2U Rack Mounted (Additional Accessories)with Built in 4 X12V/9AH batteries for (15 Minutes), (1 Year Warranty)	Ea	11	1,267.00	13,937.00
		Professional Services				
17	SRV	Devices Installation, Testing & Commissioning	Lot	1	37,500.00	37,500.00
					Total Excluding VAT	172,955.00